## ARIZONA DEPARTMENT OF TRANSPORTATION September 18, 2020 – TRANSPORTATION BOARD PROJECT AWARDS

DESCRIPTION OF WORK	TRACS #	LOW BIDDER	BOARD ACTION
DESCRIPTION OF WORK The proposed work is located in Santa Cruz County and Pima County on Interstate 19 between Milepost 21.1 and Milepost 31.8, a distance of approximately 10.7 miles. The work consists of milling the existing pavement and replacing it with new asphaltic concrete pavement with Asphaltic Concrete Friction Course (ACFC), and replacing a section of the existing asphalt pavement with Portland Cement Concrete Pavement. The work also includes installation of new cable barrier, replacing bridge barriers,	<b>PROJECT #</b> 019 SC 021 H893501C 019-A(232)T	LOW BIDDER FISHER SAND & GRAVEL CO. DBA SOUTHWEST ASPHALT PAVING	AWARD \$ 17,266,666.00
replacing guardrails, signing, restriping and other related work. The proposed work is located in Coconino County within City of Flagstaff on Business Route 40 (B40) at milepost 196.08, and approximately 0.3 miles west of the US 180 for an approximate length of 0.10 miles. The proposed work consists of replacing the existing 2-span bridge over Rio de Flag. Project will include reconstruction of east approach roadway, constructing a new anchor slab, replacing pavement markings, channel lining, over excavation of channel and other related work.	040B CN 196 H890501C B40-D(203)T	FNF CONSTRUCTION, INC.	AWARD \$ 4,942,893.52
The proposed Gilbert Road Pump Station Rehabilitation work is located in Maricopa County within the City of Mesa on US 60 at Milepost 182.15. The work consists of removing an replacing three storm drain water pumps, three propane-fueled pump engines, three rightangle gear drives, one sump pump, new slide gate with vault, new propane delivery system, new electrical controls, new gas detection system, new leveling elements, and other related work.	060 MA 182 F025101C 060-C(217)T	ARCHER WESTERN CONSTRUCTION, LLC	AWARD \$ 1,742,678.00
The proposed drainage improvement project is located in Gila County on SR 73 from MP 313.94 to MP 330.76 within Fort Apache Indian Reservation/White Mountain Apache Tribe limits. The works consists of repairing highway culvert outfalls and improving culvert outfalls to mitigate and control erosion. The work includes replacing existing barbed wire fence, placing riprap gabions and mattress, rail bank protection and other related work.	073 GI 314 F021701C 073-A(208)T	HATCH CONSTRUCTION & PAVING, INC.	AWARD \$ 421,661.30

## ARIZONA DEPARTMENT OF TRANSPORTATION September 18, 2020 – TRANSPORTATION BOARD PROJECT AWARDS

The proposed SR 24 project is located within Maricopa and Pinal Counties on SR 24. Project limits extend east from Ellsworth Road to Ironwood Drive, between MP 0.56 to MP 5.64, within the City of Mesa, Town of Queen Creek, Maricopa County, and Pinal County. The work consists of constructing new roadway extending the SR 24 freeway. The work includes excavation, embankment, concrete and asphaltic concrete paving, new concrete bridges, retaining walls, storm drain, catch basins, concrete lined channel, reinforced concrete box culverts, pavement markings, signing, traffic signals, lighting, FMS and other related work.	024 MA 000 H891501C NHPP-024-A(200)T	FNF CONSTRUCTION, INC.	AWARD \$ 76,999,508.95
The proposed work is located in Mohave County on Interstate 40, between mileposts 23.56 and 40.42, approximately 17 miles south of the City of Kingman. The proposed work consists of removing and replacing bridge decks and approach slabs, rehabilitating bridge decks using mechanical milling and polyester polymer concrete overlay. Additional work includes removing and replacing guardrail and other miscellaneous work.	040 MO 023 F016201C 040-A(228)T	FNF CONSTRUCTION, INC.	AWARD \$ 5,992,093.80
The proposed project is located in Maricopa County at the intersection of SR 347 and Old Maricopa Road within the Gila Indian River Community. The work consists of installing a new traffic signal and adding auxiliary lanes. The work includes new traffic signal equipment, placing asphaltic concrete, constructing drainage, pavement marking, signing, lighting, and related work.	347 MA 187 F020801C 347-A(212)T	AJP ELECTRIC, INC.	REJECT ALL BIDS \$ 1,482,184.16
The proposed project is located within the City of Kingman on Mohave County. The project extends for an approximate length of 0.87 miles on Stockton Hill Road, from Detroit Avenue to Airway Avenue. The work consists of signalization, signing, placing aggregate base, placement of asphaltic concrete pavement, pavement marking, and other related work.	0000 MO KNG T019101C KNG-0(210)T	AJP ELECTRIC, INC.	REJECT ALL BIDS \$ 615,289.48