

ARIZONA DEPARTMENT OF TRANSPORTATION
February 18, 2022 – TRANSPORTATION BOARD PROJECT AWARDS

DESCRIPTION OF WORK	TRACS # PROJECT #	LOW BIDDER	BOARD ACTION
<p>The proposed work is located in Pima County on Interstate 10 between milepost 237.47 and 247.89 near Marana. The proposed work consists of removing the existing asphaltic concrete surface course by milling and replacing it with a bonded wearing course overlay. The project also includes spot repair work by milling and replacement with asphaltic concrete. Additional work includes replacing pavement markings and other miscellaneous work.</p>	<p>010 PM 237 F039801C 010-D(223)T</p>	<p>FNF CONSTRUCTION, INC.</p>	<p>AWARD \$ 6,313,814.50</p>
<p>The proposed project is located in Gila County on US 60, approximately 10 miles west of Carrizo. The project begins at milepost 305.0 and extends northeast to milepost 305.5. The work consists of installing soil replacement column to repair the failed slope, seeding, and other related work.</p>	<p>060 GI 305 F043001C 060-E(222)T</p>	<p>BUESING CORP.</p>	<p>AWARD \$ 905,018.36</p>
<p>The proposed project is located in Pinal County on SR 87 at MP 137.70, 139.01, and 140.63 respectively, west of the Town of Florence. The portion of the project is located within the Gila River Indian Community. The work consists of deck overlay and scour retrofit. The deck overlay will be performed on the High Line Canal, McClellan Wash and Santa Cruz Bridges and scour retrofit will be performed on the McClellan Wash Bridge and Santa Cruz Bridge. The work includes milling roadway pavement and filling with asphaltic concrete, mechanical milling of the bridge deck and overlaying bridge deck surface with polyester polymer concrete, installing concrete floor underneath the existing bridges, pavement marking, seeding and other related works.</p>	<p>087 PN 137 F030201C 087-A(212)T</p>	<p>COMBS CONSTRUCTION COMPANY, INC.</p>	<p>AWARD \$ 1,172,854.80</p>
<p>The proposed project is located in Pinal County on Russell Road 3 miles east of Stanfield, and 9 miles west of Casa Grande. The work consists of constructing new asphalt concrete road over existing dirt road, seeding, signing, pavement marking, and other related items.</p>	<p>0000 PN PPN T018601C PPN-0(219)T</p>	<p>STORMWATER PLANS, LLC dba SWP CONTRACTING & PAVING</p>	<p>AWARD \$ 3,077,777.00</p>
<p>The proposed project is located in Maricopa County on Interstate 10 between milepost 100.0 and 105.9, east of Tonopah. The work consists of removing the existing asphaltic rubber asphaltic concrete friction course by milling and replacing with new hot mix asphalt concrete bonded overlay. The work also includes pavement marking and other related work.</p>	<p>010 MA 100 F041101C 010-A(237)T</p>	<p>FNF CONSTRUCTION, INC.</p>	<p>AWARD \$ 1,949,131.50</p>

ARIZONA DEPARTMENT OF TRANSPORTATION
February 18, 2022 – TRANSPORTATION BOARD PROJECT AWARDS

<p>The proposed work is located in Yavapai County on Interstate 40, approximately 11 miles west of Seligman at mile post 109.65. Approximate length of the project is 0.13 mile. The work consists of removing and replacing the existing bridge deck and approach slabs on both sides of the bridge and replacing existing guardrail, replacing pavement markings, and other miscellaneous work.</p>	<p>040 YV 109 F025401C 040-B(230)T</p>	<p>FNF CONSTRUCTION, INC.</p>	<p>AWARD \$ 2,677,693.40</p>
<p>The proposed work is located in Mohave County on SR 68, from Milepost 0 to Milepost 14.67. The work consists of micro-surfacing, milling and replacing the existing asphaltic concrete, concrete friction course, pavement marking and other related work.</p>	<p>068 MO 068 F040601C 068-A(208)T</p>	<p>PAVECO, INC.</p>	<p>AWARD \$ 3,589,004.00</p>
<p>The proposed work is located in Pima County on State Route 86 between milepost 166.55 and 170.84 near South Tucson. The proposed work consists of removing the existing asphaltic concrete surface course by milling and replacing it with a bonded wearing course overlay. The project also includes spot repair work by milling and replacement with asphaltic concrete. Additional work includes replacing pavement markings and other miscellaneous work.</p>	<p>086 PM 166 F040001C 086-A(225)T</p>	<p>SUNLAND ASPHALT & CONSTRUCTION, LLC</p>	<p>AWARD \$ 2,538,000.00</p>

ARIZONA DEPARTMENT OF TRANSPORTATION
February 18, 2022 – TRANSPORTATION BOARD PROJECT AWARDS

<p>The proposed project 089A CN 387 H8778 01C is located in Coconino County within the Coconino National Forest on State Route 89A, MP 387.28 to MP 387.43. The work consists of Pumphouse Wash Bridge Rehabilitation. The work includes bridge deck and railing replacement, new approach slabs, painting of the bridge, pier encasement and scour mitigation; milling and repaving; guardrail replacement; restoration of a culvert outlet; signing and striping; seeding and other related work. The proposed project 089A CN 388 H8907 01C is located in Coconino County within the Coconino National Forest on State Route 89A from MP 387.92 to MP 388.73 for location A and B and from MP 388.90 to MP 388.96 for Location C. The work consists of drainage and sediment control improvement by reducing erosion to preserve deteriorating slopes and reduce downstream pollution. The work includes installing concrete barrier, pipes, retaining wall and catch basin; gabion mattresses; roadside drainage excavation; seeding and other related work. The proposed project 089A CN 375 F0154 01C is located in Coconino County on State Route 89A at MP 375.1 and MP 389.2. The work consists of improvements to mitigate rockfall at those locations, pavement improvements, pavement marking, traffic control and other related work.</p>	<p>089A CN 388 H890701C A89-B(218)T</p> <p>089A CN 387 H877801C A89-B(217)T</p> <p>089A CN 375 F015401C A89-B(222)T</p>	<p>FISHER SAND & GRAVEL CO. DBA SOUTHWEST ASPHALT PAVING</p>	<p>AWARD \$ 11,111,111.11</p>
<p>The proposed project is located in Coconino County on SR 89A between mileposts 402.05 and 403.05 and on I-40B between mileposts 195.48 and 195.86. The work consists of removing the existing asphaltic concrete by milling and replacing it with new asphaltic concrete. Additional work includes removing and replacing existing curb and gutter, sidewalk, driveway, pavement markings, and other related work.</p>	<p>089A CN 402 F029601C A89-B(224)T</p>	<p>SUNLAND ASPHALT & CONSTRUCTION, LLC</p>	<p>AWARD \$ 3,595,500.00</p>
<p>The proposed project is located in Yuma County on US 95 between milepost 38.50 and 44.34, north of Fortuna Foothills. The work consists of removing the existing asphaltic concrete (AC) friction course by milling and replacing with new asphalt-rubber asphaltic concrete friction course (AR-ACFC). The work also includes pavement marking and other related work.</p>	<p>095 YU 038 F041301C 095-B(216)T</p>	<p>PAVECO, INC.</p>	<p>AWARD \$ 979,273.07</p>

ARIZONA DEPARTMENT OF TRANSPORTATION
February 18, 2022 – TRANSPORTATION BOARD PROJECT AWARDS

<p>The proposed project is located in Coconino County, on State Route 264 (SR 264) east of Tuba City at milepost 324.10, on the Hopi Reservation. The work consists of Moenkopi Wash (Str. # 621) bridge deck replacement. The work includes removing the existing bridge deck, barriers, and constructing a new deck with new barriers, new approach slabs, new compression seal joints, added shear studs, paint existing structural steel, abutment repair, install guardrail, pavement marking and other related work.</p>	<p style="text-align: center;">264 CN 324 F023101C 264-A(220)T</p>	<p style="text-align: center;">FNF CONSTRUCTION, INC.</p>	<p style="text-align: center;">AWARD \$ 3,031,192.80</p>
<p>The proposed work is located in Pinal County on State Route 287 between milepost 134.60 and 142.96 near Coolidge. The proposed work consists of removing the existing asphaltic concrete surface course by milling and replacing it with an Asphaltic Rubber – Asphaltic Concrete Friction Course. Additional work includes replacing pavement markings and other miscellaneous work.</p>	<p style="text-align: center;">287 PN 134 F043101C 287-B(200)T</p>	<p style="text-align: center;">PAVECO, INC.</p>	<p style="text-align: center;">AWARD \$ 1,048,974.98</p>
<p>The proposed project is located in Yuma County near the town of Wellton at Ave 28E and County 9th Street. The proposed work consists of removing and replacing the existing bridge over the Salinity Canal. The work also includes constructing the bridge approaches and other related work.</p>	<p style="text-align: center;">0000 YU YYU T024101C YYU-0(218)T</p>	<p style="text-align: center;">COMBS CONSTRUCTION COMPANY, INC.</p>	<p style="text-align: center;">AWARD \$ 723,536.09</p>