

**ARIZONA DEPARTMENT OF TRANSPORTATION**  
**October 21, 2022 – TRANSPORTATION BOARD PROJECT AWARDS**

DESCRIPTION OF WORK	TRACS # PROJECT #	LOW BIDDER	BOARD ACTION
<p>The proposed pavement rehabilitation project is located in Pima County, on Interstate 10 (I-10) within the limits of the City of Tucson, beginning at milepost 262.4 and extending east along I-10 to milepost 272. The work consists of pavement rehabilitation and bridge deck repair. The work includes removal of existing asphaltic concrete friction course by milling and replacing with new asphalt- rubber concrete friction course (AR-ACFC), placing crack seal and fog coat on the shoulders; constructing guardrail, bridge deck repair and installing conduits, traffic signs, pavement marking and highway lighting and other related work.</p>	<p>010 PM 262 F021201C 010-E(230)T</p>	<p>GRANITE CONSTRUCTION COMPANY</p>	<p>AWARD \$ 15,495,176.00</p>
<p>The proposed project is located in Pinal and Pima Counties, on Interstate 10 from milepost 219.20 to 248.13. The proposed work consists of installing conduit, fiber optic cable, pull boxes, connection to an existing DMS, CCTV, and traffic signal cabinets, construction of a fiber node building and related work.</p>	<p>010 PN 219 F043901C 010-D(224)T</p>	<p>WILLIAM CHARLES CONSTRUCTION COMPANY, LLC</p>	<p>AWARD \$ 4,975,994.90</p>

**ARIZONA DEPARTMENT OF TRANSPORTATION  
October 21, 2022 – TRANSPORTATION BOARD PROJECT AWARDS**

<p>The proposed work for project 010 PM 248 H7583 01C is located in Pima County, on 1-10 from milepost 248.03 to milepost 251.85, in the City of Tucson, Town of Marana, and unincorporated Pima County. The work consists of reconstructing 1-10 to provide four general purpose lanes in each direction. The work includes construction of bridges, Portland cement concrete pavement, asphaltic concrete pavement, drainage facilities, and mechanically stabilized earth walls. Additional work includes, pavement markings, signing, lighting, freeway management system, landscaping, aesthetics, and other related work. The proposed work for project 0000 PM PPM T0327 01C is located in the City of Tucson and unincorporated Pima County along Sunset Road, starting at the Santa Cruz River Bridge just east of Silverbell Road, and extending east to River Road. The work consists of roadway and bridge improvements including pathway connection to the Chuck Huckelberry Loop for approximately 1.06 miles of roadway construction. The work also includes construction of bridges, Portland cement concrete pavement, asphaltic concrete pavement, drainage facilities, and mechanically stabilized earth walls. Additional work includes pavement markings, signing, lighting, freeway management system, landscaping, aesthetics, and other related work.</p>	<p>010 PM 247 H758301C 010-D-(211)S</p> <p>0000 PM PPM T032701C PPM-O(268)D</p>	<p>GRANITE CONSTRUCTION COMPANY</p>	<p>AWARD \$ 170,988,897.00</p>
<p>The proposed work is located in Mohave County on Interstate 15 at milepost 27.30, approximately two miles south of Arizona and Utah Border. The proposed work consists of rehabilitating existing northbound and southbound bridge decks. The work also includes milling and paving both sides of the approach slabs to provide a smooth transition between bridges and adjacent pavements.</p>	<p>015 MO 027 F030801C 015-A(217)T</p>	<p>VASTCO, INC.</p>	<p>AWARD \$ 1,160,836.60</p>

**ARIZONA DEPARTMENT OF TRANSPORTATION**  
**October 21, 2022 – TRANSPORTATION BOARD PROJECT AWARDS**

<p>The proposed project is located in Pinal County on US 60 from Milepost 208.75 to 208.78, south of Gold Canyon City. The work consists of scour retrofit, bridge deck rehabilitation and replacing approach slabs. The work includes milling concrete deck and overlaying with Polyester Polymer Concrete (PPC), removing existing approach slabs &amp; reinstalling new approach slabs, installing new barrier, removing and installing guard rail, constructing concrete scour floor underneath the existing bridge, pavement reconstruction at the bridge approaches, pavement marking, seeding and other related works.</p>	<p style="text-align: center;">060 PN 208 F038601C 060-C(219)T</p>	<p style="text-align: center;">COMBS CONSTRUCTION COMPANY, INC.</p>	<p style="text-align: center;"><b>AWARD</b> \$ 1,307,589.15</p>
<p>The proposed work is located in Pinal County where SR 287 and SR 79B meet at the southern section of the Town of Florence. Approximate length of the project is 0.73 miles. The work consists of adding a new multi-lane roundabout at SR 287 and SR 79B and a single-lane roundabout at SR 79B and Florence Heights Drive.</p>	<p style="text-align: center;">0000 PN FLO SZ04101C FLO-0(201)T</p>	<p style="text-align: center;">COMBS CONSTRUCTION COMPANY, INC.</p>	<p style="text-align: center;"><b>REJECT ALL BIDS</b> \$ 7,543,649.40</p>
<p>The proposed project is located in Graham County on Golf Course Rd and Cottonwood Wash Rd. The roadways are approximately seven miles apart. The Golf Course Road work begins east of the Hoopes Avenue roundabout and ends approximately 600 feet west of 20th Avenue in the Town of Thatcher and the City of Safford. The Cottonwood Wash Rd work begins south of Cottonwood Wash Loop and ends approximately 200 feet east of 800 West in the Town of Pima. The work consists of constructing paved shoulders and rumble strips along both roadways. The work includes: grading roadway for pavement, asphaltic concrete, rumble strips, pavement marking, signing and other related work.</p>	<p style="text-align: center;">0000 GH GGH T030501C GGH-0(207)T</p>	<p style="text-align: center;">HATCH CONSTRUCTION &amp; PAVING, INC.</p>	<p style="text-align: center;"><b>POSTPONED</b> \$ 1,698,863.03</p>
<p>The proposed project is located in Mohave County on Beale Street, Stockton Hill Rd, Hualapai Mountain Rd, Airway Ave, Gordon Dr, Beverly Ave within the City of Kingman within the Northwest District. The proposed work consists of the installation of 12 speed feedback signs and other related work.</p>	<p style="text-align: center;">0000 MO KNG T028001C KNG-0(211)T</p>	<p style="text-align: center;">TECHNOLOGY CONSTRUCTION, INC.</p>	<p style="text-align: center;"><b>REJECT ALL BIDS</b> \$ 348,909.00</p>