

ARIZONA DEPARTMENT OF TRANSPORTATION
December 19, 2025 – TRANSPORTATION BOARD PROJECT AWARDS

DESCRIPTION OF WORK	TRACS # PROJECT #	LOW BIDDER	BOARD ACTION
The project is located in Yavapai County on US 93 between MP 156.0 and MP 172.0. The proposed work consists of pavement rehabilitation. The work includes milling and filling the existing asphaltic concrete of roadway mainline and shoulders, and milled asphalt concrete treatment at designated unpaved crossovers. The work also includes replacing existing guardrail, embankment curb, drainage improvements, joint seal replacement, seeding, applying pavement marking, installing ground-in rumble strips, delineator, and object marker updates, and other related work.	093 YV 156 F063801C 093-B(226)T	FNF CONSTRUCTION, INC.	AWARD \$ 19,479,342.06
The proposed project is located in Cochise County on Moon Canyon Road at the intersection with Tombstone Canyon Road in the City of Bisbee. The work consists of replacing the existing bridge, bridge barrier and reconstructing the roadway approaches.	0000 CH BIS T052401C BIS-0(205)T	C S CONSTRUCTION, INC.	AWARD \$ 664,769.00
The proposed project is located in Maricopa County on Missouri Avenue: from 59th Avenue to 51st Avenue; on San Miguel Avenue: from 59th Avenue to 57th Avenue; on Montebello Avenue: from 61st Avenue to 57th Avenue; on 57th Avenue: from Missouri Avenue to Bethany Home Road; and on 55th Avenue: from Missouri Avenue to Bethany Home Road, for a total length of 3.13 miles. The work consists of connecting existing sidewalks along corridors, striping and video detection for bicycle accommodations, driveway replacements, railroad crossing improvements, as well as other related work.	0000 MA GLN T037201C GLN-0(268)T	D B A CONSTRUCTION INC.	AWARD \$ 3,049,167.86
The proposed project is located in Cochise County, along Interstate 10, between mileposts 345.50 and 356.49, near Willcox. The work includes milling the existing asphaltic concrete surface course and replacing it with new asphaltic concrete and a stone matrix asphaltic concrete overlay. It also involves replacing guardrails and guardrail end terminals, repairing existing bridge decks and concrete box culverts, updating pavement markings, and performing other related work.	010 CH 345 F064301C 010-F(234)T	FNF CONSTRUCTION, INC.	AWARD \$ 21,154,661.64

ARIZONA DEPARTMENT OF TRANSPORTATION
December 19, 2025 – TRANSPORTATION BOARD PROJECT AWARDS

The proposed work is located in Santa Cruz County on I-19 at milepost 1.0. The proposed work consists of removing existing deck surfaces by mechanical milling and applying two-inch polyester polymer concrete (PPC) overlay. The project also includes milling and replacing with asphaltic concrete, replacing pavement markings, guardrail and other miscellaneous work.	019 SC 001 F070901C 019-A(245)T	GRANITE CONSTRUCTION COMPANY	AWARD \$ 3,957,733.00
The proposed project is located in Maricopa County, within the City of Phoenix, along State Route 51, from Interstate 10 (milepost 148.23) to Shea Boulevard (milepost 9.80). The work includes milling asphalt rubber–asphalt concrete friction course, repairing Portland cement concrete pavement, diamond grinding the surface of existing concrete pavement and bridge decks, repairing bridge decks and bridge joints, installing pavement markings, and performing other related work.	051 MA 000 F085801C 051-A-NFA	EMERY SAPP & SONS, INC.	AWARD \$ 17,845,579.59
The proposed project F069901C is located on US 70 in Gila County, 5 miles southwest of City of Globe within San Carlos Apache Tribe Reservation. The project begins at MP 256.5 and ends at MP 259.4. The proposed work consists of installing roadway lighting and other related works within the project limits. The proposed project T031301C is located in Gila County within San Carlos Apache Tribe approximately 5,000 feet along White Mountain Avenue north of the intersection of White Mountain Avenue and BIA 170. The work consists of the installation of roadway lighting, pavement markings, and other related work.	070 GI 256 F069901C 070-A(227)T 0000 GI ISC T031301C ISC-0(203)T	SHOW LOW CONSTRUCTION, INC.	AWARD \$ 3,601,968.28
The proposed work is located in Coconino County within the limits of Coconino National Forest, on State Route 89A, between MP 386.97 to MP 389.83, near Oak Creek Vista. The work includes upgrading existing guardrails and guardrail end terminals and other related work.	089A CN 386 F071801C A89-B(226)T	HAWK CONTRACTING LLC.	AWARD \$ 3,444,444.00
The proposed project is located on Navajo Nation and Hopi lands in Coconino County begins at Tuba City and extends east along US 160 from Milepost 321.80 to Milepost 335. The proposed work consists of mill and replaces AC, remove and replace guardrail, extend pipe culverts, pavement marking and other related work.	160 CN 321 F064401C 160-A(213)T	SUNLAND ASPHALT & CONSTRUCTION LLC.	AWARD \$ 20,475,887.67

ARIZONA DEPARTMENT OF TRANSPORTATION
December 19, 2025 – TRANSPORTATION BOARD PROJECT AWARDS

The proposed project is located in Navajo County on SR 377 south of Dry Lake from milepost 8 to milepost 13. The works consists of widening the existing roadway pavement to accommodate shoulders in both Northbound and Southbound directions on State Route 377 and install centerline and edge line rumble strips. The work also includes paving turnouts, fog coat application on the existing travel lanes and new shoulder widening; install new pipe and pipe encasement, signing, pavement marking and other related work.	377 NA 008 F066101C 377-A(203)T	SEMA CONSTRUCTION, INC.	AWARD \$ 8,455,109.07
The proposed project is located in Maricopa County, within the Town of Gilbert, for the half-mile of Mews Road east of Higley Road. The project work includes paving gravel roadway, construction of a concrete drainage channel on the south side of Mews Road, and waterline and sewer line extensions and other related work.	0000 MA GIL T033601C GIL-0(218)T	RUMMEL CONSTRUCTION, INC.	POSTPONED \$ 2,882,974.10
The proposed project 0000 PN CSG T046901C is located in the City of Casa Grande within Pinal County. The proposed work consists of extending the eastbound left turn lane at the intersection of Florence Boulevard and Peart Road, and related work. The proposed project 0000 PN CSG T047001C is located in the City of Casa Grande within Pinal County. The proposed work consists of constructing a new raised median on Florence Boulevard west of Colorado Street, and related work.	0000 PN CSG T046901C CSG-0(212)T 0000 PN CSG T047001C CSG-0(213)T	AJP ELECTRIC, INC.	AWARD \$ 381,964.40
The proposed project is located in Pinal County, eastern portion of the City of Maricopa, Arizona on approximately 0.6 miles of Murphy Road and 0.5 miles of Hartman Road from the Gila River Indian Community (GRIC) boundary to Honeycutt Road. The work consists of placing a double chip seal coat, striping, and other related work.	0000 PN MAR T054701C MAR-0-(215)T	SUNLAND ASPHALT & CONSTRUCTION LLC.	AWARD \$ 1,351,377.00
The proposed project is located in Pinal County on Battaglia Drive between Henness Road and Overfield Road, near the unincorporated area of Arizona City. The work includes widening the outside shoulders. The work also includes pavement marking, guardrail replacement, and other related work.	0000 PN PPN T044901C PPN-0(232)T	W. W. CLYDE & CO.	AWARD \$ 2,230,833.80

ARIZONA DEPARTMENT OF TRANSPORTATION
December 19, 2025 – TRANSPORTATION BOARD PROJECT AWARDS

The proposed project is located in Yuma County within the City of San Luis along Cesar Chavez Blvd between Escondido Street to Avenue E. The work consists of reconstructing the roadway along Cesar Chavez Blvd to a four lane divided roadway intersection channelization at intersecting streets, drainage facilities, asphaltic concrete, signing, pavement marking, signals, lighting, and other related work. The project also includes a one-lane roundabout at the intersection of Cesar Chavez Blvd and Escondido St / San Luis Plaza Dr.	0000 YU SLS SZ01801C SLS-0(203)A	DPE CONSTRUCTION, INC.	AWARD \$ 57,044,316.00
The proposed project is located in the Yuma County at the intersection of County 11th Street and Avenue G. The work consists of removing sharp curve and realignment of Avenue G and County 11th Street and widening to provide exclusive left and right turn lanes. The work also includes aggregate base, asphalt concrete, street light conduit and junction boxes, pavement marking, signing, and other related work.	0000 YU YUM T037801C YUM-0(223)T	DPE CONSTRUCTION, INC.	REJECT BID \$ 1,299,695.00
The proposed work is located in the city of Apache Junction. The length of the project is 2.97 miles in total which includes work along Old West Highway, from Idaho Road on the west end to Goldfield Road on the east end of the project, and Winchester Road, from Broadway Avenue on the south end to Old West Highway on the north end. The work consists of constructing a new sidewalk along the south side of Old West Highway and on the west side of Winchester Road including sections that are attached with concrete curb and gutter and sections that are detached. The work includes several box culvert extensions, bridge railing, scuppers, pedestrian access ramps, guardrail modifications, seeding, signing and pavement markings, and other related work.	0000 PN APJ T024201C APJ-0(217)T	D B A CONSTRUCTION INC.	AWARD \$ 3,620,748.15